

Controlled Decking Zone Procedures

OSHA 29 CFR §1926.761(c)(3)

(Rapids Code #0877) (O*Net/Soc Code #47-2221.00)

Test Answer Sheet

1.)	A Controlled Decking Zone may be implemented when fall exposures are greater than _15_ feet and no more
	than two stories or _30_feet.
2 \	A CD7/s control lines would be installed and unsintained between what also at one above the welling according

2.)	A CDZ's control lines must be installed and maintained between what elevations above the walking or work	ing
	surface (including sag)?	

- a) 34" and 40"
- b) 36" and 42"
- c) 39" and 45" *** ** (This is the same requirement as for the top rail of a guardrail system)
- 3.) What is the breaking strength required of the rope, wire, tape or material used to mark the boundaries of a CDZ?
 - a) There is no specified minimum breaking strength
 - b) 200lb*****
 - c) 500lb
 - d) 2000lb
- 4.) What is the maximum distance from the leading edge that the control line may be?
 - a) 90'***** (It is also limited to 90' wide)
 - b) 100'
 - c) 120'
- 5.) Employees do not need to wear harnesses while working inside a CDZ.
 - a) True
 - b) False***** (CDZ workers are subject to the same requirements as connectors. Must be able to tie off.)
- 6.) All of the following are hazards directly related to a Controlled Decking Zone EXCEPT for:
 - a) Falls from unprotected edges
 - b) Slippery walking/working surface
 - c) Tripping over materials and tools
 - d) Air quality monitoring ******
- 7.) Covers for holes and openings in a CDZ need to support at least_____ without failure
 - a) The maximum load which may be imposed at any one time
 - b) Twice the maximum load which may be imposed at any one time*****
 - c) Four times the maximum load which may be imposed at any one time

Page 1 of 2

- 8.) Metal decking and roof bundles must be _____ when environmental or jobsite conditions require, or at the end of the shift.
 - a) Returned to the ground
 - b) Secured against displacement*****
 - c) Touch-up painted
- 9.) When should holes for skylights or pipe boots be cut into a standing seam roof?
 - a) Immediately before the installation of the skylight or pipe. ****** (Even if there is no danger of falling through a small hole, screws and materials may fall down on workers below)
 - b) As soon as the dimensions are agreed upon.
 - c) Whenever there's no threat of rain.
- 10.) Is the jobsite electrician allowed to wire an HVAC unit in a Controlled Decking Zone?
 - a) Yes
 - b) No****** (Only workers directly engaged in leading edge may work in a CDZ. Even with all the proper training, electrical is not leading edge work.)
 - c) Yes, if he/she has proper training